South Western Railway Mysore Division

Examination Name: Examination for selection of post of JE/works in the pay band Rs 9300-43800 GP Rs 4200/ level 06 of pay matrix in civil Engineering Department, Mysuru Division- LDCE quota

Exam Date: 04.08.2020

Name:	Roll No:
Duration: 2 Hrs	Date:
Marks of each question: 2 Marks	Total Marks: 100 Marks
Questions to be attended: 50 nos	Total questions in exam paper: 55 nos

Instructions for candidate

- 1. All questions are objective type and having four multiple choices.
- 2. This question paper having total 55 questions from General knowledge, Technical, Rajbhasha.
- 3. Any 50 questions to be answered. More than 50 answers, each extra answer will be treated as wrong answer.
- 4. Each questions having 2 marks. Total 50 x 2 = 100 marks
- 5. There is <u>NEGATIVE MARKING</u> for each wrong answer. For every wrong answer 1/3 rd of each question will be deducted. i.e. 1/3rd of 2 marks will be deducted for every wrong answer.
- 6. Calculator, mobile or any electronic gadget are not required for this exam paper.

 Therefore use of all electronic gadgets are prohibited in exam hall.
- 7. DO NOT write your name or any other personal identity in OMR Answer Sheet.
- 8. No correction is allowed in OMR answer sheet.
- 9. This paper is in bilingual (English & Hindi language). For any discrepancy, matter on nglish version will prevail.

Instructions for evaluator.

- 1. Only 50 answers to be evaluated. More than 50 answers, each extra answer will be treated as wrong answer. Each questions having 2 marks
- 2. There is negative marking for each wrong answer. For every wrong answer 1/3 rd of each question will be deducted. i.e. 1/3rd of 2 marks will be deducted for every wrong answer.

1854

1853

Please answer only 50 questions

- 1. When was the first passenger train run in India?
 - A. 1851 B. 1852 C.

2.	In year the practice of presenting separate railway budget from the general/Union budget started. Further based on Vivek Devroy Committee recommendation, Govt announce on about merger of Railway budget in to union budget of India.
	A. 1920, 2017 B. 1924, 2016
	C. 1925, 2019 D. 1930, 2016
3.	How much distance was travelled by first train of India?
	A. 33 km B. 36 km C. 34 km D. 46 km
4.	In which of the following cities is the National Rail Museum located ?
	A. Mumbai B. New Delhi C. Hyderabad D. Mysore
5.	India's first semi high speed trainExpress which is also known as Train-18, was
	introduced on feb/2019 between section.
	a. Tejas , Lucknow-New Delhi
	b. Vande bharat, New Delhi- Varanashi
	c. Hum-safar ,Delhi-Katihar
	d. Antyodaya, Chennai tambram-Tirunelveli
6.	Shatabdi Express train was started in
	a. 1984 b. 1988 c. 1990 d. 1985
-	
7.	Which is the shortest station name in Indian Railways?
	a. Pune b. Bc c. Goa d. Ib
8.	Diesel locomotives are built in?
0.	a. Banglore b. Varanasi c. Perambur d. Hubli
	a. Dangiore D. Varanasi C. Feranibul G. Hubii
9.	Which of the following is the largest railway junction in India?
	a. Delhi b. Bhatinda Jn c. Mathura Jn d. Allahabad Jn
	d. Jenn D. Dradmadon G. Machardon d. Andriabadon
10.	Which is the fastest train in India?
	A. Gatimaan Express B. Shatabdi Express
	C. Vande Bharat Express D. Tejas Express
11.	Which Zone is the largest railway zone in India?
	A. Northern Railway B. Central Railway
	C. Eastern Railway D. Western Railway
12.	As per latest release from Railway ministry for 2019, which station is the cleanest railway station in
	Indian Railway?
	A. Mysore B. New Delhi
	C. Jodhpur D. Jaipur

13.	Division	ial authori	value of w	ork order u	ınder any zor	nal contract	which can be	sanction	ed by
	A. 2.5 L	Lakh B	. 5.0 lakhs	C. 10	0.0 lakh	D. None	of above		
	a. Alcoh b. Wet t c. Alcoh	nol % in bro thickness c nal % in blo	r measuring eath of runi of paint laye ood sample f paint laye	ning staff er. of running s	staff.				
15. A. C	0.1 mg	/liter B.	minimum re 0.2 mg/ 2 mg/lite	liter	ine in potable	water?	Allen gis		
16. A A.			s desirable li 6.5 to 8.0		lue of potable 5 to 8.5	water? D. 7.2 to	8.0		
17.	As per IR	WM, What	is TDS limit	for potable v	vater?				
	Α.	500-800	B. 500-	2000	C. 600- 2000) D.	. 600-800		
	a.	34 sq m	B. 45 s	q m	is the revised C. 54 sq m		inth area for an . 60 sq m	y staff qua	irter?
19. 1	Height of	High level	olatform sho	uld be					
		A. 75	0mm to 820	mm	B. 760 mm	to 840mm	Total Insurance		
		C 72	0 mm to 860) mm	D. 750 mm	n to 850 mm			
20.	What terrain a. c.	should be 1 in 30 1 in 20	b.	est ruling g 1 in 25 1 in 35	gradient of re	oad appro	ach of RUB in	n plain /	rolling
21.	Which ca. b. c. d.	Inspection Preparation Sanction of	of all struct on of plans a of Proposal f	ures and the	s, execution and notes property the management of the works property in the works property in the management of the mana	e in a satisfa ad measuren	actory and safe nent of works. nd revenue bud		

22. As per IR-SOD, what is minimum horizontal clearance of any telegraphic post from the nearest track? A. 2.36 m B. 2.135 m C. 2.3 m

D. 2.145 m

23.	What is desirable vertical clearance of new construction FOB over electrified track? A. 5.75 m B. 6.20 m C. 5.870 m D. 6.25 m
	What should be the extra provision of vertical allowance kept in electrified section for construction of over head structure, equipment to cater future increase of ballast cushion, sleepers thickness and deeper rail section? 225mm B. 250mm C. 275 mm D. 300 mm
25.	For ensuring quality of concrete, use A. Single size aggregates.
	A. Single size aggregates B. Two sized aggregates C. Graded aggregates D. Coarse aggregates
26.	The risk of segregation is more for a. Wetter mix b. Larger proportion of maximum is a
	 Larger proportion of maximum size of aggregates Coarser grading
	d. All of three above
27.	Higher water/cement ratio
	a. Decrease durability of concrete
	b. Increase strength of concrete
	c. Decrease workability of concrete
	d. all of above
28.	Construction joint are not generally provided in concrete
	A. Roads B. Retaining wall
	C. Lining of canal D. column
29.	Nominal cover of concrete on main reinforcement of a column (having x-section size > 200 mm) & foundation should not be less than?
	A. 25 mm, 35 mm B. 30 mm, 50 mm
	C. 35 mm 40 mm D. 40 mm, 50 mm
30.	Maximum spacing, between shear stirrups in any beam reinforcement, should not exceed a. 300 mm
	b. 0.75 d (d=effective depth of beam) for vertical stirrups
	c. d (d = effective depth of beam) for inclined stirrups at 45 degree.d. Minumim of All of above.
31:	The value of detailed estimate of any proposed work should not be more than% age above on abstract value of sanctioned work. A. 20% B 15% C. 10% D. 25%

 32. What should be the desirable thickness of each layer in earth work to get homogeneous compaction of any type of soil? A. 150-250mm B. 400-500 mm C. 200-300 mm D. 300-500 mm C. 200-300 mm D. 300-500 mm G. 200-300 mm D. 300-500 mm G. 200-300 mm D. 300-500 mm G. 200-300 mm D. 300-500 mm John Statement is false? a. OMC is required to get MDD b. Poorly graded sand and gravel with Cu>2.0 should be use in soil bank. c. Moisture content play key role in compaction of in clayey soil. d. None of above 34. As per IRWM, what is the per capita water demand for domestic use? A. 100 ltr/day B. 200 ltr/day C. 250 ltr/day D. 150 ltr/day 35. As per IRWM, what is the per passenger water demand at station platform? A. 10 ltr/day B. 15 ltr/day C. 20 ltr/day D. 25 ltr/day 36. What should be minimum slope required in valley gutter made up of plain galvanised steel sheet in cover over platform? A. 1 in 100 B. 1 in 50 C. 1 in 120 D. 1 in 140 37. For recording of Brick work, measurement should be accurate to the nearest least count of measuring tape? A. 1 mm B. 5 mm C. 10 mm D. None of the above 38. Which one is the false statement? a. In measurement for steel fabrication work, the separate weight of welding material should not be paid. b. In the measurement of steel fabrication work, the hole made for bolt, rivets should be deducted. c. The weight of nut and Bolts in build up steel section to be paid separately. d. None of the above. 39. Measurement of Steel fabrication work should be done to the nearest least count of measuring tape A. 1 mm B. 2 mm C. 5 mm D. None of the above 40. Weight of rivets to be paid @ %age of weight of riveted steel structure A. 1% B. 2% C. 3% D. 1.5% 41. Full form of QAP: A. Quality assurance plan 		
A. 150-250mm B. 400-500 mm C. 200-300 mm D. 300-500 mm C. 200 MC is required to get MDD D. Poorly graded sand and gravel with Cu>2.0 should be use in soil bank. C. Moisture content play key role in compaction of in clayey soil. d. None of above 34. As per IRWM, what is the per capita water demand for domestic use? A. 100 Itr/day D. 150 Itr/day C. 250 Itr/day D. 150 Itr/day C. 250 Itr/day D. 25 Itr/day C. 20 Itr/day D. 25 Itr/day C. 20 Itr/day D. 25 Itr/day C. 20 Itr/day D. 1 in 120 D. 1 in 140 37. For recording of Brick work, measurement should be accurate to the nearest least count of measuring tape? A. 1 mm B. 5 mm C. 10 mm D. None of the above 38. Which one is the false statement? a. In measurement for steel fabrication work, the separate weight of welding material should not be paid. b. In the measurement of steel fabrication work, the hole made for bolt, rivets should be deducted. C. The weight of nut and Bolts in build up steel section to be paid separately. d. None of the above 40. Weight of rivets to be paid @ %age of weight of riveted steel structure A. 1% B. 2 mm C. 3 mm D. None of the above	32.	What should be the desirable thickness of each layer in earth work to got be
A. 150-250mm C. 200-300 mm D. 300-500 mm D.		compaction of any type of soil ?
a. OMC is required to get MDD b. Poorly graded sand and gravel with Cu>2.0 should be use in soil bank. c. Moisture content play key role in compaction of in clayey soil. d. None of above 34. As per IRWM, what is the per capita water demand for domestic use? A. 100 ltr/day B. 200 ltr/day C. 250 ltr/day D. 150 ltr/day 35. As per IRWM, what is the per passenger water demand at station platform? A. 10 ltr/day B. 15 ltr/day C. 20 ltr/day D. 25 ltr/day 36. What should be minimum slope required in valley gutter made up of plain galvanised steel sheet in cover over platform? A. 1 in 100 B. 1 in 50 C. 1 in 120 D. 1 in 140 37. For recording of Brick work, measurement should be accurate to the nearest least count of measuring tape? A. 1 mm B. 5 mm C. 10 mm D. None of the above 38. Which one is the false statement? a. In measurement for steel fabrication work, the separate weight of welding material should not be paid. b. In the measurement of steel fabrication work, the hole made for bolt, rivets should be deducted. c. The weight of nut and Bolts in build up steel section to be paid separately. d. None of the above. 39. Measurement of Steel fabrication work should be done to the nearest least count of measuring tape A. 1 mm B. 2 mm C. 5 mm D. None of the above		A. 150-250mm B. 400-500 mm
 a. OMC is required to get MDD b. Poorly graded sand and gravel with Cu>2.0 should be use in soil bank. c. Moisture content play key role in compaction of in clayey soil. d. None of above 34. As per IRWM, what is the per capita water demand for domestic use? A. 100 ltr/day B. 200 ltr/day C. 250 ltr/day D. 150 ltr/day 35. As per IRWM, what is the per passenger water demand at station platform? A. 10 ltr/day B. 15 ltr/day C. 20 ltr/day D. 25 ltr/day 36. What should be minimum slope required in valley gutter made up of plain galvanised steel sheet in cover over platform? A. 1 in 100 B. 1 in 50 C. 1 in 120 D. 1 in 140 37. For recording of Brick work, measurement should be accurate to the nearest least count of measuring tape? A. 1 mm B. 5 mm C. 10 mm D. None of the above 38. Which one is the false statement? a. In measurement for steel fabrication work, the separate weight of welding material should not be paid. b. In the measurement of steel fabrication work, the hole made for bolt, rivets should be deducted. c. The weight of nut and Bolts in build up steel section to be paid separately. d. None of the above. 39. Measurement of Steel fabrication work should be done to the nearest least count of measuring tape A. 1 mm B. 2 mm C. 3 mm D. None of the above 40. Weight of rivets to be paid @ %age of weight of riveted steel structure A. 1% B. 2% C. 3% D. 1.5% 41. Full form of QAP: 		C. 200-300 mm D. 300-500 mm
 a. OMC is required to get MDD b. Poorly graded sand and gravel with Cu>2.0 should be use in soil bank. c. Moisture content play key role in compaction of in clayey soil. d. None of above 34. As per IRWM, what is the per capita water demand for domestic use? A. 100 ltr/day B. 200 ltr/day C. 250 ltr/day D. 150 ltr/day 35. As per IRWM, what is the per passenger water demand at station platform? A. 10 ltr/day B. 15 ltr/day C. 20 ltr/day D. 25 ltr/day 36. What should be minimum slope required in valley gutter made up of plain galvanised steel sheet in cover over platform? A. 1 in 100 B. 1 in 50 C. 1 in 120 D. 1 in 140 37. For recording of Brick work, measurement should be accurate to the nearest least count of measuring tape? A. 1 mm B. 5 mm C. 10 mm D. None of the above 38. Which one is the false statement? a. In measurement for steel fabrication work, the separate weight of welding material should not be paid. b. In the measurement of steel fabrication work, the hole made for bolt, rivets should be deducted. c. The weight of nut and Bolts in build up steel section to be paid separately. d. None of the above. 39. Measurement of Steel fabrication work should be done to the nearest least count of measuring tape A. 1 mm B. 2 mm C. 3 mm D. None of the above 40. Weight of rivets to be paid @ %age of weight of riveted steel structure A. 1% B. 2% C. 3% D. 1.5% 41. Full form of QAP: 	22	Which at the state of the state
 b. Poorly graded sand and gravel with Cu>2.0 should be use in soil bank. c. Moisture content play key role in compaction of in clayey soil. d. None of above 34. As per IRWM, what is the per capita water demand for domestic use? A. 100 ltr/day B. 200 ltr/day C. 250 ltr/day D. 150 ltr/day 35. As per IRWM, what is the per passenger water demand at station platform? A. 10 ltr/day B. 15 ltr/day C. 20 ltr/day D. 25 ltr/day 36. What should be minimum slope required in valley gutter made up of plain galvanised steel sheet in cover over platform? A. 1 in 100 B. 1 in 50 C. 1 in 120 D. 1 in 140 37. For recording of Brick work, measurement should be accurate to the nearest least count of measuring tape? A. 1 mm B. 5 mm C. 10 mm D. None of the above 38. Which one is the false statement? a. In measurement for steel fabrication work, the separate weight of welding material should not be paid. b. In the measurement of steel fabrication work, the hole made for bolt, rivets should be deducted. c. The weight of nut and Bolts in build up steel section to be paid separately. d. None of the above. 39. Measurement of Steel fabrication work should be done to the nearest least count of measuring tape A. 1 mm B. 2 mm C. 5 mm D. None of the above 40. Weight of rivets to be paid @ %age of weight of riveted steel structure A. 1% B. 2% C. 3% D. 1.5% 41. Full form of QAP: 	33.	
 Moisture content play key role in compaction of in clayey soil. None of above 34. As per IRWM, what is the per capita water demand for domestic use? A. 100 ltr/day B. 200 ltr/day C. 250 ltr/day D. 150 ltr/day 35. As per IRWM, what is the per passenger water demand at station platform? A. 10 ltr/day B. 15 ltr/day C. 20 ltr/day D. 25 ltr/day 36. What should be minimum slope required in valley gutter made up of plain galvanised steel sheet in cover over platform? A. 1 in 100 B. 1 in 50 C. 1 in 120 D. 1 in 140 37. For recording of Brick work, measurement should be accurate to the nearest least count of measuring tape? A. 1 mm B. 5 mm C. 10 mm D. None of the above 38. Which one is the false statement? a. In measurement for steel fabrication work, the separate weight of welding material should not be paid. b. In the measurement of steel fabrication work, the hole made for bolt, rivets should be deducted. c. The weight of nut and Bolts in build up steel section to be paid separately. d. None of the above. 39. Measurement of Steel fabrication work should be done to the nearest least count of measuring tape A. 1 mm B. 2 mm C. 5 mm D. None of the above 40. Weight of rivets to be paid @ %age of weight of riveted steel structure A. 1% B. 2% C. 3% D. 1.5% 41. Full form of QAP: 		
 34. As per IRWM, what is the per capita water demand for domestic use? A. 100 ltr/day B. 200 ltr/day C. 250 ltr/day D. 150 ltr/day 35. As per IRWM, what is the per passenger water demand at station platform? A. 10 ltr/day B. 15 ltr/day C. 20 ltr/day D. 25 ltr/day 36. What should be minimum slope required in valley gutter made up of plain galvanised steel sheet in cover over platform? A. 1 in 100 B. 1 in 50 C. 1 in 120 D. 1 in 140 37. For recording of Brick work, measurement should be accurate to the nearest least count of measuring tape? A. 1 mm B. 5 mm C. 10 mm D. None of the above 38. Which one is the false statement? a. In measurement for steel fabrication work, the separate weight of welding material should not be paid. b. In the measurement of steel fabrication work, the hole made for bolt, rivets should be deducted. c. The weight of nut and Bolts in build up steel section to be paid separately. d. None of the above. 39. Measurement of Steel fabrication work should be done to the nearest least count of measuring tape A. 1 mm B. 2 mm C. 5 mm D. None of the above 40. Weight of rivets to be paid @ %age of weight of riveted steel structure A. 1% B. 2% C. 3% D. 1.5% 41. Full form of QAP: 		Moisture content play key role in compaction of its description of its
A. 100 ltr/day C. 250 ltr/day D. 150 ltr/day 35. As per IRWM, what is the per passenger water demand at station platform? A. 10 ltr/day B. 15 ltr/day C. 20 ltr/day D. 25 ltr/day 36. What should be minimum slope required in valley gutter made up of plain galvanised steel sheet in cover over platform? A. 1 in 100 B. 1 in 50 C. 1 in 120 D. 1 in 140 37. For recording of Brick work, measurement should be accurate to the nearest least count of measuring tape? A. 1 mm B. 5 mm C. 10 mm D. None of the above 38. Which one is the false statement? a. In measurement for steel fabrication work, the separate weight of welding material should not be paid. b. In the measurement of steel fabrication work, the hole made for bolt, rivets should be deducted. c. The weight of nut and Bolts in build up steel section to be paid separately. d. None of the above. 39. Measurement of Steel fabrication work should be done to the nearest least count of measuring tape A. 1 mm B. 2 mm C. 5 mm D. None of the above 40. Weight of rivets to be paid @ %age of weight of riveted steel structure A. 1% B. 2% C. 3% D. 1.5%		d. None of above
A. 100 ltr/day C. 250 ltr/day D. 150 ltr/day 35. As per IRWM, what is the per passenger water demand at station platform? A. 10 ltr/day B. 15 ltr/day C. 20 ltr/day D. 25 ltr/day 36. What should be minimum slope required in valley gutter made up of plain galvanised steel sheet in cover over platform? A. 1 in 100 B. 1 in 50 C. 1 in 120 D. 1 in 140 37. For recording of Brick work, measurement should be accurate to the nearest least count of measuring tape? A. 1 mm B. 5 mm C. 10 mm D. None of the above 38. Which one is the false statement? a. In measurement for steel fabrication work, the separate weight of welding material should not be paid. b. In the measurement of steel fabrication work, the hole made for bolt, rivets should be deducted. c. The weight of nut and Bolts in build up steel section to be paid separately. d. None of the above. 39. Measurement of Steel fabrication work should be done to the nearest least count of measuring tape A. 1 mm B. 2 mm C. 5 mm D. None of the above 40. Weight of rivets to be paid @ %age of weight of riveted steel structure A. 1% B. 2% C. 3% D. 1.5%		A STATE OF THE PARTY OF THE PAR
A. 100 ltr/day C. 250 ltr/day D. 150 ltr/day 35. As per IRWM, what is the per passenger water demand at station platform? A. 10 ltr/day B. 15 ltr/day C. 20 ltr/day D. 25 ltr/day 36. What should be minimum slope required in valley gutter made up of plain galvanised steel sheet in cover over platform? A. 1 in 100 B. 1 in 50 C. 1 in 120 D. 1 in 140 37. For recording of Brick work, measurement should be accurate to the nearest least count of measuring tape? A. 1 mm B. 5 mm C. 10 mm D. None of the above 38. Which one is the false statement? a. In measurement for steel fabrication work, the separate weight of welding material should not be paid. b. In the measurement of steel fabrication work, the hole made for bolt, rivets should be deducted. c. The weight of nut and Bolts in build up steel section to be paid separately. d. None of the above. 39. Measurement of Steel fabrication work should be done to the nearest least count of measuring tape A. 1 mm B. 2 mm C. 5 mm D. None of the above 40. Weight of rivets to be paid @ %age of weight of riveted steel structure A. 1% B. 2% C. 3% D. 1.5%	34.	As per IRWM, what is the per capita water demand for domestic use?
35. As per IRWM, what is the per passenger water demand at station platform? A. 10 ltr/day B. 15 ltr/day C. 20 ltr/day D. 25 ltr/day 36. What should be minimum slope required in valley gutter made up of plain galvanised steel sheet in cover over platform? A. 1 in 100 B. 1 in 50 C. 1 in 120 D. 1 in 140 37. For recording of Brick work, measurement should be accurate to the nearest least count of measuring tape? A. 1 mm B. 5 mm C. 10 mm D. None of the above 38. Which one is the false statement? a. In measurement for steel fabrication work, the separate weight of welding material should not be paid. b. In the measurement of steel fabrication work, the hole made for bolt, rivets should be deducted. c. The weight of nut and Bolts in build up steel section to be paid separately. d. None of the above. 39. Measurement of Steel fabrication work should be done to the nearest least count of measuring tape A. 1 mm B. 2 mm C. 5 mm D. None of the above 40. Weight of rivets to be paid @ %age of weight of riveted steel structure A. 1% B. 2% C. 3% D. 1.5% 41. Full form of QAP:		A. 100 ltr/day B. 200 ltr/day
A. 10 ltr/day B. 15 ltr/day C. 20 ltr/day D. 25 ltr/day 36. What should be minimum slope required in valley gutter made up of plain galvanised steel sheet in cover over platform? A. 1 in 100 B. 1 in 50 C. 1 in 120 D. 1 in 140 37. For recording of Brick work, measurement should be accurate to the nearest least count of measuring tape? A. 1 mm B. 5 mm C. 10 mm D. None of the above 38. Which one is the false statement? a. In measurement for steel fabrication work, the separate weight of welding material should not be paid. b. In the measurement of steel fabrication work, the hole made for bolt, rivets should be deducted. c. The weight of nut and Bolts in build up steel section to be paid separately. d. None of the above. 39. Measurement of Steel fabrication work should be done to the nearest least count of measuring tape A. 1 mm B. 2 mm C. 5 mm D. None of the above 40. Weight of rivets to be paid @ %age of weight of riveted steel structure A. 1% B. 2% C. 3% D. 1.5%		C. 250 ltr/day D. 150 ltr/day
A. 10 ltr/day B. 15 ltr/day C. 20 ltr/day D. 25 ltr/day 36. What should be minimum slope required in valley gutter made up of plain galvanised steel sheet in cover over platform? A. 1 in 100 B. 1 in 50 C. 1 in 120 D. 1 in 140 37. For recording of Brick work, measurement should be accurate to the nearest least count of measuring tape? A. 1 mm B. 5 mm C. 10 mm D. None of the above 38. Which one is the false statement? a. In measurement for steel fabrication work, the separate weight of welding material should not be paid. b. In the measurement of steel fabrication work, the hole made for bolt, rivets should be deducted. c. The weight of nut and Bolts in build up steel section to be paid separately. d. None of the above. 39. Measurement of Steel fabrication work should be done to the nearest least count of measuring tape A. 1 mm B. 2 mm C. 5 mm D. None of the above 40. Weight of rivets to be paid @ %age of weight of riveted steel structure A. 1% B. 2% C. 3% D. 1.5%	25	As non IDMAA what is at
C. 20 ltr/day D. 25 ltr/day 36. What should be minimum slope required in valley gutter made up of plain galvanised steel sheet in cover over platform? A. 1 in 100 B. 1 in 50 C. 1 in 120 D. 1 in 140 37. For recording of Brick work, measurement should be accurate to the nearest least count of measuring tape? A. 1 mm B. 5 mm C. 10 mm D. None of the above 38. Which one is the false statement? a. In measurement for steel fabrication work, the separate weight of welding material should not be paid. b. In the measurement of steel fabrication work, the hole made for bolt, rivets should be deducted. c. The weight of nut and Bolts in build up steel section to be paid separately. d. None of the above. 39. Measurement of Steel fabrication work should be done to the nearest least count of measuring tape A. 1 mm B. 2 mm C. 5 mm D. None of the above 40. Weight of rivets to be paid @ %age of weight of riveted steel structure A. 1% B. 2% C. 3% D. 1.5%	33,	
36. What should be minimum slope required in valley gutter made up of plain galvanised steel sheet in cover over platform? A. 1 in 100 B. 1 in 50 C. 1 in 120 D. 1 in 140 37. For recording of Brick work, measurement should be accurate to the nearest least count of measuring tape? A. 1 mm B. 5 mm C. 10 mm D. None of the above 38. Which one is the false statement? a. In measurement for steel fabrication work, the separate weight of welding material should not be paid. b. In the measurement of steel fabrication work, the hole made for bolt, rivets should be deducted. c. The weight of nut and Bolts in build up steel section to be paid separately. d. None of the above. 39. Measurement of Steel fabrication work should be done to the nearest least count of measuring tape A. 1 mm B. 2 mm C. 5 mm D. None of the above 40. Weight of rivets to be paid @ %age of weight of riveted steel structure A. 1% B. 2% C. 3% D. 1.5% 41. Full form of QAP:		
sheet in cover over platform? A. 1 in 100 B. 1 in 50 C. 1 in 120 D. 1 in 140 37. For recording of Brick work, measurement should be accurate to the nearest least count of measuring tape? A. 1 mm B. 5 mm C. 10 mm D. None of the above 38. Which one is the false statement? a. In measurement for steel fabrication work, the separate weight of welding material should not be paid. b. In the measurement of steel fabrication work, the hole made for bolt, rivets should be deducted. c. The weight of nut and Bolts in build up steel section to be paid separately. d. None of the above. 39. Measurement of Steel fabrication work should be done to the nearest least count of measuring tape A. 1 mm B. 2 mm C. 5 mm D. None of the above 40. Weight of rivets to be paid @ %age of weight of riveted steel structure A. 1% B. 2% C. 3% D. 1.5% 41. Full form of QAP:		25 talyddy 5. 25 talyddy
sheet in cover over platform? A. 1 in 100 B. 1 in 50 C. 1 in 120 D. 1 in 140 37. For recording of Brick work, measurement should be accurate to the nearest least count of measuring tape? A. 1 mm B. 5 mm C. 10 mm D. None of the above 38. Which one is the false statement? a. In measurement for steel fabrication work, the separate weight of welding material should not be paid. b. In the measurement of steel fabrication work, the hole made for bolt, rivets should be deducted. c. The weight of nut and Bolts in build up steel section to be paid separately. d. None of the above. 39. Measurement of Steel fabrication work should be done to the nearest least count of measuring tape A. 1 mm B. 2 mm C. 5 mm D. None of the above 40. Weight of rivets to be paid @ %age of weight of riveted steel structure A. 1% B. 2% C. 3% D. 1.5% 41. Full form of QAP:	36.	What should be minimum slope required in valley gutter made up of plain galvanised steel
 37. For recording of Brick work, measurement should be accurate to the nearest least count of measuring tape? A. 1 mm B. 5 mm C. 10 mm D. None of the above 38. Which one is the false statement? a. In measurement for steel fabrication work, the separate weight of welding material should not be paid. b. In the measurement of steel fabrication work, the hole made for bolt, rivets should be deducted. c. The weight of nut and Bolts in build up steel section to be paid separately. d. None of the above. 39. Measurement of Steel fabrication work should be done to the nearest least count of measuring tape A. 1 mm B. 2 mm C. 5 mm D. None of the above 40. Weight of rivets to be paid @ %age of weight of riveted steel structure A. 1% B. 2% C. 3% D. 1.5% 41. Full form of QAP: 		sheet in cover over platform ?
measuring tape? A. 1 mm B. 5 mm C. 10 mm D. None of the above 38. Which one is the false statement? a. In measurement for steel fabrication work, the separate weight of welding material should not be paid. b. In the measurement of steel fabrication work, the hole made for bolt, rivets should be deducted. c. The weight of nut and Bolts in build up steel section to be paid separately. d. None of the above. 39. Measurement of Steel fabrication work should be done to the nearest least count of measuring tape A. 1 mm B. 2 mm C. 5 mm D. None of the above 40. Weight of rivets to be paid @ %age of weight of riveted steel structure A. 1% B. 2% C. 3% D. 1.5% 41. Full form of QAP:		A. 1 in 100 B. 1 in 50 C. 1 in 120 D. 1 in 140
measuring tape? A. 1 mm B. 5 mm C. 10 mm D. None of the above 38. Which one is the false statement? a. In measurement for steel fabrication work, the separate weight of welding material should not be paid. b. In the measurement of steel fabrication work, the hole made for bolt, rivets should be deducted. c. The weight of nut and Bolts in build up steel section to be paid separately. d. None of the above. 39. Measurement of Steel fabrication work should be done to the nearest least count of measuring tape A. 1 mm B. 2 mm C. 5 mm D. None of the above 40. Weight of rivets to be paid @ %age of weight of riveted steel structure A. 1% B. 2% C. 3% D. 1.5% 41. Full form of QAP:	37.	. For recording of Brick work, measurement should be accurate to the population
 A. 1 mm B. 5 mm C. 10 mm D. None of the above 38. Which one is the false statement? a. In measurement for steel fabrication work, the separate weight of welding material should not be paid. b. In the measurement of steel fabrication work, the hole made for bolt, rivets should be deducted. c. The weight of nut and Bolts in build up steel section to be paid separately. d. None of the above. 39. Measurement of Steel fabrication work should be done to the nearest least count of measuring tape A. 1 mm B. 2 mm C. 5 mm D. None of the above 40. Weight of rivets to be paid @ %age of weight of riveted steel structure A. 1% B. 2% C. 3% D. 1.5% 41. Full form of QAP: 		measuring tape?
 a. In measurement for steel fabrication work, the separate weight of welding material should not be paid. b. In the measurement of steel fabrication work, the hole made for bolt, rivets should be deducted. c. The weight of nut and Bolts in build up steel section to be paid separately. d. None of the above. 39. Measurement of Steel fabrication work should be done to the nearest least count of measuring tape A. 1 mm B. 2 mm C. 5 mm D. None of the above 40. Weight of rivets to be paid @ %age of weight of riveted steel structure A. 1% B. 2% C. 3% D. 1.5% 41. Full form of QAP: 		
 a. In measurement for steel fabrication work, the separate weight of welding material should not be paid. b. In the measurement of steel fabrication work, the hole made for bolt, rivets should be deducted. c. The weight of nut and Bolts in build up steel section to be paid separately. d. None of the above. 39. Measurement of Steel fabrication work should be done to the nearest least count of measuring tape A. 1 mm B. 2 mm C. 5 mm D. None of the above 40. Weight of rivets to be paid @ %age of weight of riveted steel structure A. 1% B. 2% C. 3% D. 1.5% 41. Full form of QAP: 		
should not be paid. b. In the measurement of steel fabrication work, the hole made for bolt, rivets should be deducted. c. The weight of nut and Bolts in build up steel section to be paid separately. d. None of the above. 39. Measurement of Steel fabrication work should be done to the nearest least count of measuring tape A. 1 mm B. 2 mm C. 5 mm D. None of the above 40. Weight of rivets to be paid @ %age of weight of riveted steel structure A. 1% B. 2% C. 3% D. 1.5%	38.	The state of the s
 b. In the measurement of steel fabrication work, the hole made for bolt, rivets should be deducted. c. The weight of nut and Bolts in build up steel section to be paid separately. d. None of the above. 39. Measurement of Steel fabrication work should be done to the nearest least count of measuring tape A. 1 mm B. 2 mm C. 5 mm D. None of the above 40. Weight of rivets to be paid @ %age of weight of riveted steel structure A. 1% B. 2% C. 3% D. 1.5% 41. Full form of QAP: 		
be deducted. C. The weight of nut and Bolts in build up steel section to be paid separately. d. None of the above. 39. Measurement of Steel fabrication work should be done to the nearest least count of measuring tape A. 1 mm B. 2 mm C. 5 mm D. None of the above 40. Weight of rivets to be paid @ %age of weight of riveted steel structure A. 1% B. 2% C. 3% D. 1.5% 41. Full form of QAP:		
 d. None of the above. 39. Measurement of Steel fabrication work should be done to the nearest least count of measuring tape A. 1 mm B. 2 mm C. 5 mm D. None of the above 40. Weight of rivets to be paid @ %age of weight of riveted steel structure A. 1% B. 2% C. 3% D. 1.5% 41. Full form of QAP: 		
 d. None of the above. 39. Measurement of Steel fabrication work should be done to the nearest least count of measuring tape A. 1 mm B. 2 mm C. 5 mm D. None of the above 40. Weight of rivets to be paid @ %age of weight of riveted steel structure A. 1% B. 2% C. 3% D. 1.5% 41. Full form of QAP: 		c. The weight of nut and Bolts in build up steel section to be paid separately.
measuring tape A. 1 mm B. 2 mm C. 5 mm D. None of the above 40. Weight of rivets to be paid @ %age of weight of riveted steel structure A. 1% B. 2% C. 3% D. 1.5% 41. Full form of QAP:		
measuring tape A. 1 mm B. 2 mm C. 5 mm D. None of the above 40. Weight of rivets to be paid @ %age of weight of riveted steel structure A. 1% B. 2% C. 3% D. 1.5% 41. Full form of QAP:	24	to design and the second secon
A. 1 mm B. 2 mm C. 5 mm D. None of the above 40. Weight of rivets to be paid @ %age of weight of riveted steel structure A. 1% B. 2% C. 3% D. 1.5% 41. Full form of QAP:	3	
 40. Weight of rivets to be paid @ %age of weight of riveted steel structure A. 1% B. 2% C. 3% D. 1.5% 41. Full form of QAP: 		Ended to the Zu
A. 1% B. 2% C. 3% D. 1.5% 41. Full form of QAP:		
41. Full form of QAP:	4	0. Weight of rivets to be paid @ %age of weight of riveted steel structure
		A. 1% B. 2% C. 3% D. 1.5%
	4	11 Full form of OAR:
	4	

B. QUALITY APPROVE PROCEDURE C. QUICK ACTION PLAN D. QUALITY ACTION PLAN 42. FULL FORM OF WPS Α. WELDING PROCEDURE SCHEDULE B. WORK PROGRESS SCHEDULE C. WORK PROCEDURE SPECIFICATION WELDING PROCEDURE SPECIFICATION D. 43. What is the width of broad gauge railway line in india A. 1760 mm B. 1670 mm C. 1676 mm D. 1673 mm 44. Full form of IR- USS A. Indian Railway Union Standard Schedule B. Indian Railway Unified standard specification C. Indian Railway universal standard schedule D. Indian Railway universal standard specification 45. Full form of IR-USSOR A. INDIAN RAILWAY UNION STANDARD SCHEDULE OF RATES B. INDIAN RAILWAY UNIVERSAL STANDARD SPECIFICATION OF RATE C. INDIAN RAILWAY UNIFIED SCHEDULE STANDARD OF RATE INDIAN RAILWAY UNIFIED STANDARD SCHEDULES OF RATE D. What is the recommended slope ratio for soil water pipe A. 1:12 B. 1:20 C. 1:30 D. 1:40 47. Arch bridge having span 6 m, and rise 3 m, danger level will be-A. 3 m below from crown. B. 2 m below from crown. C 2 m above from springing level. D. None of above. For designing any railway bridge, danger level shall be kept at : 48. a) the level which provides adequate vertical clearances; b) the level of water which is likely to cause an unduly large afflux, say more than 0.5 m, which may cause large scour endangering the bridge; and c) the water level which if exceeded may cause excessive scour endangering the bridge. d) All of above What is the schedule frequency of interior distempering for station building? 49. Once in 6 months A. Once in 2 year B.

C.

D.

Once a year

None of the above

50.	The marking of highest flood level (year in figures of 100mm deep) line should be painted as
	A. 50mm bright white line over 100 mm broad red line centrally for length of 600mm on up stream side of bridge.
	B. 50mm bright white line over 100 mm broad red line centrally for length of 600mm on Down stream side of bridge.
	C. 50mm bright red line over 100 mm broad white line centrally for length of 600mm on up stream side of bridge
	D. 50mm bright red line over 100 mm broad white line centrally for length of 600mm on down stream side of bridge
	Which part of the Constitution contains provisions regarding Official Language? A. Part XVI B. Part XVI C. Part XIX D. None of above.
52.	Who is the Chairman of the Zonal Official Language Implementation Committee? A. General Manager/SWR/UBL B. CPO/SWR C. AGM/SWR D. PCPO/SWR
53.	As per Rajbhasha Act 1976 sub rule -02, How many groups of Indian states are classified for use of Hindi Rajbhasha? A. Four B. Three C. Five D. Two
54.	As per Rajbhasha Act 1976 sub rule -02 regarding use of Rajbhasha, Karnataka state fall under which classification of state group?
	A. A B. B C. C D. None of above
55.	As per Rule 11 (2) of Official Language Rules 1976, Format and title of registers used in the office of the Central Government should be written in following language A. Hindi, English B. English, Kannada C. English, Sanshkrit D. None of above
	End of Paper